

NATIONAL CERTIFIED TESTING LABORATORIES

FIVE LEIGH DRIVE • YORK, PENNSYLVANIA 17406 • TELEPHONE (717) 846-1200 FAX (717) 767-4100

www.nctlinc.com

ASTM E283-04(12) ASTM E330-14 ASTM E331-00(09) ASTM E547-00(09)

STRUCTURAL PERFORMANCE TEST REPORT SUMMARY

RENDERED TO:

Alumin Techno LLC Silitskogo Str. 12-211 220075 FEZ Minsk Minsk area, Minsk region The Republic of Belarus

MODEL/TYPE: "CW2" Fixed Curtain Wall

TITLE	SUMMARY OF RESULTS
Air Infiltration 75 Pa (1.57 psf)	0.10 L/s/m ² (0.02 cfm/ft ² measured)
Air Infiltration 300 Pa (6.24 psf)	0.15 L/s/m ² (0.03 cfm/ft ² measured)
Water Penetration Resistance	574.6 Pa (12.0 psf)
Design Pressure	± 3591.02 Pa (75.0 psf)
Uniform Load Structural Test	± 5386.53 Pa (112.5 psf)

Test Completion Date: 06/26/14

Reference must be made to Report Number NCTL-110-16401-1 dated 08/20/14 for complete test sample description and data.

National Certified Testing Laboratories

DIGITAL SIGNATURE

Jay Leader Technician



NATIONAL CERTIFIED TESTING LABORATORIES

FIVE LEIGH DRIVE • YORK, PENNSYLVANIA 17406 • TELEPHONE (717) 846-1200 FAX (717) 767-4100

www.nctlinc.com

STRUCTURAL PERFORMANCE TEST REPORT

Report Number NCTL-110-16401-1

Report Date 08/20/14

Report To Alumin Techno LLC

Selitskogostr. 12-211220075 FEZ Minsk

Minsk area, Minsk region The Republic of Belarus

Starting Test Date 05/2 Ending Test Date 06/2

05/20/14 06/26/14

Specification ASTM E283-04(12), "Standard Test Method for Determining Rate of Air Leakage

Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure

Differences Across the Specimen."

ASTM E331-00(09), "Standard Test Method for Water Penetration of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference."

ASTM E547-00(09), "Standard Test Method for Water Penetration of Exterior

Windows, Skylights, Doors and Curtain Walls by Cyclic Static Air Pressure Difference."

ASTM E330-14, "Standard Test Method for Structural Performance of Exterior Windows, Curtain Walls and Doors by Uniform Static Air Pressure Difference."

Description of Sample Tested

Note: All dimensions are in the order (Width x Height x Thickness) unless otherwise noted.

Model/Type "CW2"

Configuration Fixed Curtain Wall

Frame Size 2438 mm x 2438 mm (96" x 96")

Fixed Viewing Area (2) 1149 mm x 2343 mm (45.25" x 92.25")

Frame Type Extruded aluminum with vinyl-wrapped foam thermal breaks

Joint Construction Frame/ Intermediate

Butt-type aluminum clip (4) screw

Glazing Components

Overall 25.15 mm (0.990") nominal

Glass Thickness (2) Lites of 6 mm (0.224") nominal tempered glass

Spacer Type/ Size 13.77 mm (0.542") Desiccant-filled aluminum spacer (Type A1-D)

Glazing System Exterior glazed against EPDM hollow bulb single-leaf gasket and held-in-place with

silicone and (4) aluminum glazing clips evenly spaced at the verticals

Weatherstrip

Type (1) Strips of EPDM hollow bulb single-leaf gasket

Location Intermediate glazing

Alumin Techno LLC NCTL-110-16401-1

Type (1) Strip of EPDM hollow bulb single-leaf gasket Location All frame glazing members and exterior trim

Auxiliary

Type Rigid vinyl insert

Location All frame members secured with evenly spaced screws

Type Rigid vinyl joinery cover

Location Frame and intermediate joinery

Type Aluminum trim
Location Exterior of frame

Type Aluminum shim

Location Evenly spaced at the glazing perimeter

Type Aluminum spacer fastened with (2) screws
Location Frame/ intermediate located at aluminum shims

Type Auxiliary aluminum glazing molding

Location Glazing track

Reinforcement

Type Extruded aluminum tube
Thickness 2.16 mm (0.085")
Location Jambs and intermediate

Interior & Exterior

Surface Finish White painted aluminum

Installation Method The window was installed in a 50.8 mm by 254 mm (2" x 10") spruce-pine-fir lumber

test buck with (1) 16 gauge 50.8 mm (2") by 152.4 mm (6") by 152 mm (0.060") thick steel strap located at the ends of each jamb and intermediate. Each strap was secured to the frame/ intermediate with (4) #12 x 19 mm (0.75") flat head screws and (4) #8 x 31.75 mm (1.25") drywall screws to the buck. The exterior perimeter was

sealed with silicone.

Test Results

<u>Test Method</u> <u>Test</u>

ASTM E283-04(12) Air Leakage Resistance

Information at 75 Pa (1.6 psf)

Total Air Flow = 0.76 L/s (1.6 cfm)Extraneous Air Leakage Tare = 0.28 L/s (0.6 cfm)

Infiltration Rate/ Area = $0.10 \text{ L/s/m}^2 (0.02 \text{ cfm/ft}^2)$

Information at 300 Pa (6.24 psf)

Total Air Flow = 1.93 L/s (4.1 cfm) Extraneous Air Leakage Tare = 1.04 L/s (2.2 cfm)

Infiltration Rate/ Area = $0.15 \text{ L/s/m}^2 (0.3 \text{ cfm/ft}^2)$

Test Method Test

ASTM E547-00(09) Water Resistance Test

ASTM E331-00(09)

3.4 L/ (min• m²) (5.0 gph/ft²)

No Leakage after 4 cycles of 5 minutes at 574.6 Pa (12.0 psf) No Leakage after 1 cycle of 15 minutes at 574.6 Pa (12.0 psf) Alumin Techno LLC NCTL-110-16401-1

Test Method

<u>Test</u>

ASTM E330-14 Uniform Load Deflection at Design Pressure

No damage after positive 3591.02 Pa (75.0 psf) held for 10 seconds No damage after negative 3591.02 Pa (75.0 psf) held for 10 seconds

Measured Deflection Positive = 27.54 mm (1.084 inches)
Measured Deflection Negative = 27.64 mm (1.088 inches)

Test Method ASTM E330-14 Test

Uniform Load Structural Test

No damage after positive 5386.53 Pa (112.5 psf) held for 10 seconds No damage after negative 5386.53 Pa (112.5 psf) held for 10 seconds

Measured Permanent Set $_{Positive} = 5.11 \text{ mm}$ (0.201 inches) Measured Permanent Set $_{Negative} = 3.81 \text{ mm}$ (0.150 inches)

NOTE: Deflection and Permanent Set measurements taken on the intermediate over a

2350 mm (92.5") span.

This test report was prepared by National Certified Testing Laboratory (NCTL), for the exclusive use of the above named client and it does not constitute certification of this product. The results are for the particular specimen tested and do not imply the quality of similar or identical products manufactured or installed from specifications identical to the tested product. The test specimen was supplied to NCTL by the above named client. No conclusions of any kind regarding the adequacy or inadequacy of the glass in the test specimen are to be drawn from the ASTM E330 test. Foam tape is mounted to the perimeter of the test buck prior to clamping to the test wall. NCTL is a testing lab and assumes that all information provided by the client is accurate and does not guarantee or warranty any product tested or installed.

Detailed drawings were available for laboratory records and compared to the test specimen at the time of this report. Component drawings were reviewed for product verification. The bill of materials contains details with any deviations noted. Ambient conditions during the referenced testing are available upon request. A copy of this report along with representative sections of the test specimen will be retained by NCTL. This report does not constitute certification or approval of the product, which may only be granted by a certification program validator or recognized approval entity. All tests were conducted in full compliance with the referenced specifications and/or test methods. This report may not be reproduced, except in full, without the written consent of NCTL.

National Certified Testing Laboratories

DIGITAL SIGNATURE

Jay Leader

Technician

Robert H. Zeiders, P.E.

Vice-President Engineering & Quality

NJL/ drm Attachments

Appendix A – Drawing & Revision Summary

APPENDIX A

Section 1:

Component Drawings, with Applicable Part Numbers, Manufacturing and Modeling Details, were reviewed (as submitted) for Product Verification (Reference: NCTL-110-16401-1)


See Attached Documentation; any deviations noted.


Note: The above referenced component drawings along with representative sections of the test specimen will be retained per procedure by NCTL. This testing facility assumes that all information provided by the client is accurate.


Section 2:

<u>Identification</u> <u>Date</u> <u>Page & Revision</u>

Original Issue 08/20/14 Not Applicable







<u>}</u>	4	m	ф	4	4	32	72	4	7	-	-	-	100	4	51	12	80	100	ф	-	ф	
Description	Horizontal mullion extrusion L= 46 1/4" 490*	Vertical mulion extrusion L= 96" 4.90"	Reinforcement molding extrusion L= 12' 290*	Auxiliary molding L= 93 1/4" 245*	Auxiliary molding L= 46 1/4" L45*	Pressure plate	1" Insulated glass (1/4"x1/2"x1/4") 46 1/4" x 93 1/4"	Side plastic insert L= 46 5/8" L90*	Side plastic insert L= 96" 290"	Foam gasket L= 944"	Rubber gasket L= 384*	Rubber gasket L= 564 1/4"	Rubber gasket	Glass shim	Fixator	Shim	Sheer block for F50,0206	Horizontal mullion end cap	Drain sleeve	16 GA Aluminum flashing L= 384 1/2"	16 GA Steel mounting plate 2' x 5"	
Article	F50.0103	F50.0206	F50.0303	F50,1702	F50,1702	F50.1964	lG unit	F50.0902	F50.0903	F50.1921	FRK 17	FRK 14	FRK42	F50.0941	F50.1946	F50,1945	F50.0943-03	F50.0921	F50.0923	N/A	NIA	1
Mustration	<u></u>			n	n	ß		£C	:#c		Œ	B		C		(III)		U		* "	- ::	?

Professional Grade construction aroup inc 701 309 St. Breaklyn W 11222 incl. 718.382.403

PREPARED BY:

а 9

Screw Screw

#8 x 1 1/4" Philips flat head, zinc plated steel screw #8 x 1 1/2" Philips flat head, zinc plated steel screw

#12 x 1" Philips flat head, zinc plated steel screw

ALUTECH SRO

Q-L

Description Screw

Article

Mustration

9 88 24

#8 x 1/2" Philips flat head, zinc plated steel screw

#8 x 1/2" Philips pan head, zinc plated steel screw

MARIE

5 Leigh Drive York, PA 1740

DATE REVISION

PROJECT ADDRESS:

ю	Ф	4	4	32	7	4	2	-	-	-	100	4	12	12	ω	60	ф	-	ω	60	
Vertical mullion extrusion L= 96" 4.90"	Reinforcement molding extrusion L= 12" £90*	Auxiliary molding L= 93 1/4" 2.45*	Auxiliary molding L= 46 1/4" L45*	Pressure plate	1" Insulated glass (1/4"x1/2"x1/4") 46 1/4" x 93 1/4"	Side plastic insert L= 46 5/8" 290*	Side plastic insert L= 96^ 290*	Foam gasket L= 944"	Rubber gasket L= 384"	Rubber gasket L= 564 1/4"	Rubber gasket	Glass shim	Fixator	Shim	Sheer block for F50,0206	Horizontal mullion end cap	Orain sleeve	16 GA Aluminum flashing L= 384 1/2"	16 GA Steel mounting plate 2" x 6"	Plastic shim	
F50,0206	F50.0303	F50,1702	F50.1702	F50.1964	lG unit	F50.0902	F50.0903	F50.1921	FRK 17	FRK 14	FRK42	F50.0941	F50.1946	F50,1945	F50.0943-03	F50.0921	F50.0923	N/A	N/A	N/A	
F		n	n	ß		:	: #c		Ø	原				(===				* " *	-		

	,	***		
24	38	24		
Screw	Screw	Screw		
#12 x 3/4" Philips flat head, zinc plated steel screw	#8 x 5/8" Philips pan head, zinc plated steet screw	#12 x 3/4" Philips pan head, zinc plated steel screw	BILL OF MATERIAL	CURTAIN WALL AXO VIEW
MARKAT		and a	BILL OF	CURTAIL
			, we	

ALL CRAWINGS SPECTICATIONS AND COPIES INTERFOR FURWARIED BY POSESCORAL GRAPE CONSTRUCTION ARE AND SIALL REVIANT IS PROPIETY. HER PARE NOT TO BE USED ON THIS OR ANY OTHER PROJECT UNLESS WRITTEN FERMINSSOON IS GREEN.

ALL RIGHTS RESERVED

APPROVED

SPECIAL HOTES:

DO HOT SCALE DRAWINGS

ALL DIMENSIONS TO BE PISLO VERVIED PHTOR
TO ARY FABRICATION.

BILL OF MATERIAL

DATE: 12.12.2013

DRAWN BY: AG

DRAWING TITLE:

SIZE: B

DRAWING No:

CHECKED BY: AA

DA OF DA

Frie name: GRUCTURAL TESTS STRUCTURAL GALED GUNTARY WALL SETSY D-004 BALLE SEQ

B-004

REPORT NO. NCTL-110- 1648-1 TEST SPECIMEN COMPLIES ANY DEVIATION SO NOTED STATE TO THE STATE OF THE STATE TEST DATE 4/24/14

9	of	9